

---

Quality Work by Qualified Workers

December 28, 2021

Customer: Galveston Park Board

Location: Dellanera RV Park / 10901 San Louis Pass RD

Project: Elevated 600-amp Service

Thank you for the opportunity to provide an estimate to you on the following scope of work.

Qualifications:

All work is to be performed during normal business hours. Job pricing is to Buy Board rates # 638-21.

Please expect a 36hr outage during the transition from the existing service to the new.

1. Construct main service platform. Base flood level of the area is 17', Platform will be 1FT above base flood level (18' to deck floor). Install stairwell to platform for emergency and CenterPoint egress. Platform will be installed roughly 50' to the south of the existing service to maintain clearance of CenterPoint's equipment. Consult and coordinate all engineering and surveys.
2. Install new stainless-steel CT can and CenterPoint meter can at platform. CenterPoint meter can will be painted carbon steel or aluminum if available.
3. Install new 600-amp stainless steel fused disconnect at platform.
4. Install new underground feeders and risers to service pole.
5. Dig up existing building feeds and route to new elevated 600amp fused disconnect.
6. Demo old service once new service is connected. Concrete slab will remain.
7. Pull permits and coordinate with all crafts.
8. All hardware will be stainless steel and or equal to. All conduit will be PVC.

Total: \$ 114,494.00

Optional Temporary Generator: 14,277.09

Please expect a 3hr outage to connect temporary generator and a 3hr outage to disconnect.

This above price excludes tax and is good for 30 days unless otherwise noted.

There will be a 3% processing fee on all credit/debit card purchases.

Thank you,

Chad Theobald

(409-682-0334)